

PORT OF MIAMI TUNNEL CONSTRUCTION SCHEDULE (Updated 9/2013)


PROJECT COMPONENTS



LEGEND



Watson Island Construction: Moving frontage road south and shifting eastbound and westbound lanes on MacArthur Causeway to make room in median for the tunnel dig-in site.



MacArthur Bridge Work: Adding one more lane in each direction to add capacity for the tunnel traffic.



Eastbound/Westbound Tunnel work: Mining using a 43 ft. Tunnel Boring Machine, construction of structures inside tunnel, build out of emergency exits, and mechanical and electrical installation.



Dodge Island Construction: Removal of bridge separating inbound cruise traffic from outbound cargo traffic and creating new roadway network to make room for tunnel portal entrance and exit.

